

BRUHAT BANGALORE MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bangalore - 64

APPROVED SCHEDULE - 'B'

Name of Work:- Improvements to roads and construction of RCC drains at Basavalingappanagara and surrounding areas in Ward No. 03

Sl	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate In Words
1	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1)	Cum	1823.76	Rs. 215.28	Rupees Two Hundred Fifteen And Paise Twenty Eight Only
2	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222, I No-27.18)	Cum	586.45	Rs. 5,421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centring shuttering cost of material HOM of machinery curing etc., complete excluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&I WTD S.R 2018-19)	Cum	599.20	Rs. 7,070.20	Rupees Seven Thousand Seventy And Paise Twenty Only
4	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&I WTD S.R 2018-19)	Ton	43.17	Rs. 73,992.24	Rupees Seventy Three Thousand Nine Hundred Ninety Two And Paise Twenty Four Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

ಕಾರ್ಯದರ್ಶಿ ಅಭಿಮಾನಿಗಳು
ಯಶವಂತ ವಿಠಲ
ಬಿ.ಬಿ.ಎಂ.ಪಿ. ಬೆಂಗಳೂರು - 560064

Sl	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate In Words
5	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	1256.40	Rs.2,337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
6	Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	79.20	Rs.5,418.00	Rupees Five Thousand Four Hundred Eighteen Only
7	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation etc., complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWD SR 2018-19)	Nos	2258.00	Rs.432.48	Rupees Four Hundred Thirty Two And Paise Forty Eight Only
8	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWD SR 2018-19)	Sqm	254.00	Rs.84.80	Rupees Eighty Four And Paise Eighty Only
9	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials separately complete as per specifications. MORTH Specification No. 202 with 8km lead= (I No-18.47, P No-140)	Cum	330.00	Rs.973.42	Rupees Nine Hundred Seventy Three And Paise Forty Two Only
10	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum, Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rakers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, including groove cutting charges, joint filler, separation membrane of impermeable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of	Cum	198.00	Rs.5,210.96	Rupees Five Thousand Two Hundred Ten And Paise Ninety Six Only

Executive Engineer-3
KRIDL, BBMP, Bangalore

ಶಾಖಾ ಮುಖ್ಯ ಅಧಿಕಾರಿ
ಪ್ರಾ.ಪಂ. ಬೆಂಗಳೂರು
ಇ.ಇ.ಎಂ.ಎ. ವಿಭಾಗ - 560084

Sl	Description	Unit	Approved Quantity	Approved Rate Technical Manager (West) KRIDL, BBMP.	
				Rate	Rate In Words
11	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and dlisc etc. with all lead and lift. (Page No 176 Item No 22.7)	Sqm	1320.00	Rs.72.08	Rupees Seventy Two And Paise Eight Only

Signature of Contractor
Executive Engineer-3
KRIDL, BBMP, Bangalore

Signature of Executive Engineer,
Yelahanka Division,
BBMP, Bangalore-64